of work:Development Works at Dobhighat in Ward No-13 Mallasandra Ward

Schedule-B

Sl No	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs)	In words (Rs)
1	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavatedsurface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. specification etc.. Complete as per the Direction of Engineer In-Charge	Cum	78.30	237.60	Rupees Two Hundred Thirty Seven And Paise Sixty Only
2	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m.after breaking of clods complete as per specifications,specification. etc.. Complete as per the Direction of Engineer In-Charge	Cum	39.15	305.64	Rupees Three Hundred Five And Paise Sixty Four Only
3	Excavation by manual means for foundation of buildings, water supply & sanitary lines and electrical conduits etc., either in pits or in trenches 1.50m and above in width, in soft rock not exceeding 1.50mtrs in depth including stacking the excavated stuff clear from edges of excavation with lead upto 50mt including cost of explosives, labour, HOM of equipment complete as per specifications, specification. etc.. Complete as per the Direction of Engineer In-Charge	Cum	26.10	953.64	Rupees Nine Hundred Fifty Three And Paise Sixty Four Only
4	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. etc.. Complete as per the Direction of Engineer In-Charge	Cum	18.49	5449.68	Rupees Five Thousand Four Hundred Forty Nine And Paise Sixty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner

	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs)	In words (Rs)
	ng available excavated earth (excluding rock) in sides n of foundations upto plinth in layers not exceeding 20 ns. in depth, compacting each deposited layer by mming after watering with lead upto 50 m. and lift upto ..5 m. including cost of all labour complete as per specifications. Specification.etc.. Complete as per the Direction of Engineer In-Charge	Cum	146.81	82.08	Rupees Eighty Two And Paise Eight Only
	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm cum and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103 1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, Unties, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fiHets Etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications, etc.. Complete as per the Direction of Engineer In-Charge	Cum	269.50	6876.36	Rupees Six Thousand Eight Hundred Seventy Six And Paise Thirty Six Only
7	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. etc.. Complete as per the Direction of Engineer In-Charge	Sqm	36.25	249.48	Rupees Two Hundred Forty Nine And Paise Forty Eight Only
8	Providing and removing centering, shuttering, strutting, Sqm. propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. etc.. Complete as per the Direction of Engineer In-Charge	Sqm	226.20	395.28	Rupees Three Hundred Ninety Five And Paise Twenty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner

Description of Work	Unit	Qty	Sanctioned Rate	
			In Figures (Rs)	In words (Rs)
oviding T.M.T steel reinforcement for R.C.C work ıcluding straightening, cutting, bending, hooking, placing n position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT bars Fe 500 etc.. Complete as per the Direction of Engineer In-Charge	Tonne	36.38	65455.56	Rupees Sixty Five Thousand Four Hundred Fifty Five And Paise Fifty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER (Project)
Project Division
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Zone, Bangalore-73.

Scanned by CamScanner